



PRECAST POLE BASES

FASTER, HIGH QUALITY AND CUSTOMIZABLE

► Faster and Easier to Install

Atlas Precast Pole Bases are conduit-ready and use less time, labor and materials than site-cast or poured-in-place methods.

► Consistently High Quality

Our pole bases are constructed under climate-controlled conditions to guarantee a high standard of quality and finish.

► Customizable to Your Exact Specs

We know one size doesn't fit all. Base diameter, length, bolt patterns, ground wire, and conduit options can all be customized to your specs.



A BETTER, FASTER WAY TO CONSTRUCT POLE BASES



1 Attach lifting bracket to pole base.



2 Lift pole base to vertical orientation.



3 Place into hole, run wiring through conduit.



4 Fill/tamp the hole and level the base.









SCAN HERE
FOR QUOTE





PRECAST POLE BASES

FASTER, HIGH QUALITY AND CUSTOMIZABLE

	ATLAS PRECAST POLE BASES	POURED BASES
LOOK	Precast - Clean <i>*Beauty Ring Available</i> 	Poured - Candy Stripe from Sonotube
CONCRETE STRENGTH	5,000 PSI 	3,500 PSI
INSTALL TIME	45 Minutes 	3+ Days
UNIFORMITY	Consistent High Quality  Constructed under Climate Controlled Conditions	Weather Dependant
SCHEDULE FLEXIBILITY	Install When You are Ready 	Dependent on Concrete Company's Schedule
# OF VENDORS	Just One Vendor for Contractors  1 - Atlas	Multiple Vendors for Contractors 1 - Concrete 3 - Anchor Bolts 2 - Rebar 4 - Sonotube